

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-23163-00-00
Spot: NWSESESW Sec/Twnshp/Rge: 11-26S-4E
500 feet from S Section Line, 3190 feet from E Section Line
Lease Name: LADD A Well #: 21
County: BUTLER Total Vertical Depth: 2712 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2200		
CIBP		2374		
PROD	5.5	2711		250 SX
SURF	8.625	267		165 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/31/2017 12:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JONATHAN HILL WitnessType: PARTIAL
Date/Time Plugging Completed: 05/31/2017 12:30 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

SIMMONS RIG TO WELL. DYNA LOG SET CIBP AT 1915'. DUMP BAIL 2 SX CEMENT ON TOP. RUN TUBING TO 720'. QES LOADED HOLE. MIX AND SPOT 70 SX CLASS A 3% CC, 40# HULLS. TRIP OUT. LET SET 1 1/2 HOURS. WIRELINE TAG CEMENT AT 376'. LOAD HOLE AND IT STAYS FULL. DYNA LOG PERF HOLES AT 310'. QES GOT CIRCULATION OUT 8 5/8". MIX AND PUMP 100 SX 60/40 POZMIX, 4% GEL. 2% CC. CIRCULATE GOOD CEMENT. DAM UP AND FILL CELLAR. DONE 12:30 PM.

Perfs:

Top	Bot	Thru	Comments
2392	2396		
2341	2348		
1974	1979		
1960	1966		

INVOICE
24080 77

Remarks: TICKET #53361.

Plugged through: TBG

District: 02

Signed Jonathan Hill
(TECHNICIAN)