

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-20,021-0000
LEASE NAME Chaddick "A"
WELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1980 Ft. from S Section Line
1980 Ft. from E Section Line

LEASE OPERATOR Pickrell Drilling Company, Inc.
ADDRESS 110 N. Market, Suite 205 Wichita, Kansas 67202

SEC. 31 TWP. 20S RGE. 20 (E) or (W)
COUNTY Pawnee

PHONE(S) (316) 262-8427 OPERATORS LICENSE NO. 5123

Date Well Completed 9-20-67

Character of Well D&A

Plugging Commenced 2-13-98

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-13-98

The plugging proposal was approved on 2-13-98 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippian Depth to Top 4362 Bottom 4382 T.D. 4382

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	267	8 5/8"	267'	None
		0	4381	5 1/2"	4381'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
CIBP @ 4275, (perfs below BP at 4363-4364 & 4374-4378, Loaded hole thru 2 3/8" tubing.
Spotted 35sx of 60-40 poz at 3660'. Pulled tubing up to 3000' and spotted 35sx 60-40 poz, POOH w/tbg Perforated at 600 ft Hook up to 5 1/2" and pump 130sx 60-40 poz, squeeze to 900#, Shut in w/200#. Hook up to annulus and pump 20sx 60-40 poz. Shut in with 500#.

Name of Plugging Contractor Allied Cementing Company, Inc. License No. N/A

Address P.O. Box 31 - Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pickrell Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack Gurley (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jack Gurley

(Address) Jack Gurley
110 N. Market, Suite 205
Wichita, Kansas 67202



SUBSCRIBED AND SWORN TO before me this 18th day of June, 19 98

Verdelia Lewis
Notary Public

My Commission Expires: 6-06-2002