

15.145.20742.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-20.742

LEASE NAME Steffen

WELL NUMBER #2-E

SPOT LOCATION 150"N/C NE NE

SEC. 30 TWP. 20 RGE. 20 (E) of (W)

COUNTY Pawnee

Date Well Completed _____

Plugging Commenced 9-14-84

Plugging Completed 9-21-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pickrell Drilling Company

ADDRESS Box 1303, Great Bend, Kansas 67530

PHONE # (316) 793-6010 OPERATORS LICENSE NO. 5123

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? 1

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 4316'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	217'	None
				4-1/2"	4309'	2646.47'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Dumped sand to 4250' and 4 sacks cement. Shot casing at 3400', 3000', and 2750'. Pulled 64 joints of 4-1/2" casing. Allied squeezed well with 6 sacks hulls, 15 sacks gel, 50 sacks cement, 10 sacks gel, 2 sacks hulls, released plug and pumped 125 sacks 60/40 pozmix cement with 2% added gel added gel and 3% calcium chloride. Maximum pressure was 800 psi and shut in 450 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss.

SEP 25 1984

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 24th day of September, 1984

NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

My Commission expires:

Iona M. Leatherman
Notary Public