

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County. Sec. 30 Twp. 20 Rge. (E) 20W (W)

Location as "NE/CNW/SW" or footage from lines C SE NW  
Lease Owner Lario Oil & Gas Company  
Lease Name Daisy P. Beltz Well No. 1  
Office Address 301 S. Market, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 2 19 66  
Application for plugging filed September 6 19 66  
Application for plugging approved (verbal) September 2 19 66  
Plugging commenced September 2 19 66  
Plugging completed September 2 19 66  
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 4396 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	525	Cem. 300 sacks

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 460'. Mixed 30 sacks cement through drill pipe.  
Set solid plug at 40', 10 sacks cement, 2 sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 7 1966

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.  
Address 514 Orpheum Building, Wichita, Kansas 67201

STATE OF Kansas COUNTY OF Sedgwick, ss.  
G. R. Kelsey (employee/owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] 301 S. Market, Wichita, Kansas 67202 (Address)

SUBSCRIBED AND SWORN to before me this 6th day of September, 19 66

[Signature] Notary Public.

My commission expires July 21, 1970

Lario Oil & Gas Company  
 No. 1 Daisy P. Beltz  
 Cen. SE NW Sec. 30-20S-20W  
 Pawnee County, Kansas

Date Commenced: August 23, 1966  
 Date Completed: September 2, 1966  
 Drilling Contractor: Gabbert-Jones, Inc.  
 Total Depth: 4396'  
 I.P. - P. & A.

Casing Record:

8 5/8" 525' Cem. 300 sacks

<u>Formation</u>	<u>Depth</u>	<u>Geological Tops:</u>	
Surface clay, shale & shells	130	Elev.	2210' D.F.
Shale	135		2213' K.B.
Sand	316	Anhydrite	1391' (+822)
Shale	525	Heebner	3735' (-1522)
Shale & shells	830	Fort Scott	4296' (-2083)
Sand	1040	Cherokee	4311' (-2098)
Red bed	1391	Mississippian	4378' (-2165)
Anhydrite	1430		
Red bed & shale	1985		
Shale	2350		
Shale & lime	2465		
Lime	2783		
Lime & shale	3455		
Lime	4396		

**RECEIVED**  
 STATE CORPORATION COMMISSION

SEP 7 1966

CONSERVATION DIVISION  
 Wichita, Kansas