

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME SAXTON B

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 19 TWP. ZOSRGE 20W (X) (W)

COUNTY PAWNEE

Date Well Completed MAY 1, 1980

Plugging Commenced OCT 24, 1985

Plugging Completed OCT 29, 1985

LEASE OPERATOR W.E. CARL - HAWKS BROS

ADDRESS 1117 CENTENNIAL HAYS, KS

PHONE#(913) 628-8819 OPERATORS LICENSE NO. 5752

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? DODGE CITY

Is ACO-1 filed? NO If not, is well log attached? WITH CP-1

Producing Formation MISSISSIPPIAN Depth to Top 4341 Bottom 4349 T.D. 4349

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
MISSISSIPPI	OIL & WATER	4341	4349	8 5/8	425	0
				4 1/2	4341	2300

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

SAND FROM 4349 TO 4290 - 5 SX CEMENT ABOVE SAND. PULLED 2300'
CASING PUMPED 300# HULLS; 15 SX GEL; 50 SX 60/40 POZ; 10 SX GEL;
100# HULLS; 150 SX 60/40 POZ.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor NESS COUNTY WELL SERVICE License No. 7527

Address PO Box J. NESS CITY, KS

STATE OF KANSAS COUNTY OF ELLIS, ss.

DENNIS BARRY (Employee of Operator) or ~~(Operator)~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dennis Barry

(Address) 1117 CENTENNIAL HAYS, KS

SUBSCRIBED AND SWORN TO before me this 22nd. day of November, 19 85

EVELYN KORBE
STATE NOTARY PUBLIC
Ellis County, Kansas
My Appt. Expires _____

My Commission Expires: July 25, 1988

Evelyn Korbe
Notary Public

STATE CORPORATION COMMISSION

12-18-1985

DEC 18 1985

WELL LOG
Saxton B #1
C SE/4 NE/4 Sec. 19-20S-20W
Pawnee County, Kansas

Name of Operator: Geodessa Corporation
Suite 703 American National Bank Bldg.
818 17th Street
Denver, CO 80202

Date Completed: May 9, 1980

FROM	TO	
0	430	Surface
430	1378	Shale and Red Bed
1378	1405	Anhydrite
1405	1795	Shale and Red Bed
1795	2785	Shale
2785	3022	Shale and Shells
3022	4347	Shale
4347		Total Depth

STATE OF KANSAS

COUNTY OF BARTON ss

George E. Miller, Jr., President of Blue Goose Drilling Co., Inc.
being first duly sworn on oath says: That I have knowledge of the facts,
statements and matters herein contained and the log of the above described
well as filed and that the same are true and correct.

George E. Miller, Jr.
George E. Miller, Jr.

Subscribed and sworn before me this 13th day of May, 1980..

Mary Ann Schwab
Notary Public Barton County

My Commission Expires 8-1-81



RECEIVED
STATE CORPORATION COMMISSION

OCT 17 1980

CONSERVATION DIVISION
Wichita, Kansas