


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Pawnee County, Sec. 19 Twp. 20S Rge. 20 (E) (W) X
Location as "NE/CNW/SW" or footage from lines SW NE SWNW
Lease Owner Beardmore Drilling Company
Lease Name Franz Well No. 1
Office Address 700 120 Building Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 7-24-68 19
Application for plugging approved 7-25-68 19
Plugging commenced 8-10-68 19
Plugging completed 9-11-68 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation Depth to top Bottom Total Depth of Well 4370 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	379	None
				5 1/2	None	3407

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in.
Cleaned out cellar. Sanded to 4350'. Dumped 5 sacks of cement. Working pipe.
Shot pipe at 3850' and 3750'.
Working pipe. Circulating. Spotted 70 bbl of oil.
Working pipe. Shot pipe at 3600' and 3520'.
Working pipe. Shot pipe at 3410'. Pulling pipe.
Squeezed well with 18 sacks of mud - 75 sacks of cement - 1 sacks of hulls and 25 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

DESCRIBED AND SWORN TO before me this 13 day of September, 19 68

Notary Public. (Signature)
Commission expires May 27, 1969

ROTARY DRILLING LOG

Operator: Beardmore Drilling Company
 FRANZ #1, SWNW Section 19-20S-20W
 Pawnee County, Kansas

Contractor: Rains & Williamson
 Oil Co., Inc.

Commenced: 11-25-67

Completed: 12-5-67 (Rotary)

Formations:

Surface Clay	40'
Shale & Shale Streaks	225'
Shale & Shells	380'
Shale	741'
Anhydrite (Blaine)	748'
Shale	845'
Sand	1039'
Red Beds	1400'
Anhydrite	1435'
Shale	1675'
Shale & Lime	2245'
Lime & Shale	2550'
Lime	2640'
Lime & Shale	2905'
Shale & Lime	3495'
Lime & Shale	3776'
Lime	4365'
Miss. Chert	4370'
Rotary Total Depth	4370'

Remarks: Set 8-5/8" surface casing at 379' w/ 225 sacks common, 2% Ca.Cl.

Set 5 1/2" csng. at 4365' w/75 sacks common cement.


RECEIVED
 STATE CORPORATION COMMISSION
 JUL 25 1968
 CONSERVATION DIVISION
 Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.


 Wilson Rains

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 8th day of December, 1967.


 Sherry Gish Notary Public

My Commission Expires:
 June 30, 1971