

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Pawnee SEC. 19 TWP. 20S RGE. 20W E/W  
Location as in quarters or footage from lines:  
C of SW SW


Locate Well  
correctly on above  
Section Platt.

Lease Owner Tenneco Oil Company  
Lease Name Beltz #2 Well No. \_\_\_\_\_  
Office Address Box 1485 Great Bend, Kansas 67530  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 7-17-82  
Plugging completed 7-21-82  
Reason for abandonment of well or producing formation  
Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4377'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	332'	none
				5-1/2"	4372'	2441'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Plugged off bottom with sand to 4300' and ran 5 sacks cement. Shot pipe @3610',  
3325', 3035', 2810', 2600', 2440'. Pulled a total of 58 joints of 5-1/2" casing.  
Plugged surface with 3 sacks hulls, 15 sacks gel, 70 sacks cement, 1 sack hulls,  
15 sacks gel, released plug and displaced with 80 sacks cement.  
Plugging Complete.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 26 1982

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347 Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd. day of July, 19 82

My Commission expires:



Irene Hoover  
Notary Public.

## DRILLERS LOG

Beltz No. 2

CASING RECORD:	COMPANY:	Solar Oil Company	DESCRIPTION:
8 5/8" @ 322'	CONTRACTOR:	Red Tiger Drilling Company	C SW SW
w/235 sx cement	COMMENCED:	April 16, 1968	19-20S-20W
5 1/2" @ 4372.5'	COMPLETED:	April 26, 1968	Pawnee Co.,
w/100 sx cement			Kansas
TOTAL DEPTH: 4377'			ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	40	
Shale & Shells	40	323	
Shale	323	610	
Red Bed	610	742	
Gypsum-Blaine	742	753	
Red Bed	753	838	
Sand	838	1044	
Shale w/Sand	1044	1406	
Anhydrite	1406	1438	
Shale	1438	1500	
Shale & Shells	1500	2115	
Shale & Lime	2115	2685	
Lime	2685	2820	
Lime & Shale	2820	3545	
Lime	3545	3720	
Lime & Shale	3720	3875	
Lime	3875	4145	
Lime & Shale	4145	4205	
Lime	4205	4365	
Mississippi	4365	4377	

RECEIVED  
STATE CORPORATION COMMISSIONER

MAY 12 1968

CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

*Harold R. Martin*  
Harold R. Martin

Subscribed and sworn to before me this 30th day of April, 1968.

*Betty M. Maloney*  
Notary Public

My Commission Expires:

3-22-71