

RECEIVED

NOV 13 2001
 KCC WICHITA

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Saxton "A"

WELL NUMBER 1

660 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 19 TWP. 20 RGE. 20W (E) or (W)

COUNTY Pawnee

LEASE OPERATOR John J. Darrah, Jr.

ADDRESS 225 N. Market #300, Wichita, KS 67202

PHONE#(316) 263-2243 OPERATORS LICENSE NO. 5088

Character of Well OIL

(Oil, Gas, G&A, SWD, Input, Water Supply Well)

Date Well Completed _____

Plugging Commenced 9/26/01

Plugging Completed 10/4/01

The plugging proposal was approved on _____ location _____ (date)

by Richard Lacey (KCC District Agent's Name).

is ACO-1 filed? unknown if not, is well log attached? see plugging application

Producing Formation Mississippian Depth to Top 4308 Bottom 4322 T.O. 4322

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippian	Oil	4308-22		8 5/8"	289	3 feet
				4 1/2"	4308	3 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Bullheaded 2 sks hulls and 20 sks 60/40 poz w/ 15 sks hulls to plug open hole. Perf'd @ 1400 and 600, ran tubing to 1400' and pumped 110 sacks cement to surface in 4 1/2" pulled tubing, pumped 45 sks cement + 1 hulls in 4 1/2" water out 8 5/8" could not pump into 8 5/8 @ 500 psi. On 10/4 pumped 15 sks into 4 1/2", pumped 135 sks into 8 5/8-4 1/2 annulus @ 1 bpm @ 500 psi down to 1 bpm @ 850 psi.

Name of Plugging Contractor Cheyenne Well Service License No. 6454

Address P.O. Box 384, Ness City, KS 67560-0384

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John J. Darrah, Jr.

STATE OF Kansas COUNTY OF Sedgwick, ss.

G.P. Stoepfelwerth (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) G.P. Stoepfelwerth

(Address) 225 N. Market, #300, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 9th day of November, 19 2001

Susan Utterback
 Notary Public

My Commission Expires: Sept. 7, 2002



OR