

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-23,268-0000

LEASE NAME Burditt

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

4620 Ft. from S Section Line

4620 Ft. from E Section Line

LEASE OPERATOR Bankoff Oil Company

SEC. 21 TWP. 20 RGE. 23 (E) or (W)

ADDRESS Box 700657, Tulsa, OK 74170

COUNTY Ness

PHONE# (316) 262-2784 OPERATORS LICENSE NO. 6040

Date Well Completed 7-13-88

Character of Well D&A

Plugging Commenced 7-13-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-14-88

Did you notify the KCC District Office prior to plugging this well? Yes 7-13-88

Which KCC Office did you notify? State Plugger Richard Lacey

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4430

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size  | Put in | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 295    | None       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump mud to 1530'; 1st plug from 1530' to 1330' w/50 sx; pump mud to 800'. 2nd plug from 800' to 480' w/80 sx; pump mud to 300'. 3rd plug from 300' to 140' w/40 sx; pump mud to 40'. 4th plug from 40' to surface w/wiper plug & 15 sx in rathole. All cement 60/40 posmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. RECEIVED 542

Address 801 Union Center, Wichita, KS 67202 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgwick, ss. JUL 27 1988

Jack K. Wharton

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have carefully examined the facts, statements, and matters herein contained and the log of the above-described well and have filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801 Union Center  
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 26th day of July, 19 88

Notary Public

Commission Expires: 12-29-90

