

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broad
Wichita, Kansas

Pawnee County, Sec. 10 Twp. 20S Rge. 16 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW NE

Lease Owner Franco Central Oil Company

Lease Name Peterson Well No. 1

Office Address 4th National Bank Bldg. - Wichita

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed March 19 1959

Application for plugging filed March 19 1959

Application for plugging approved March 19 1959

Plugging commenced March 19 1959

Plugging completed March 19 1959

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3790 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1070'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud. Set bottom plug @ 300' with 20 sx cement. Set top plug @ 35' with 1/2 sx hulls and 10 sacks cement. Filled to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAR 25 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company

Address Box 173 - Russell, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
George A. Angle (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle

580 4th Nat'l Bank Bldg. - Wichita
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 1959

My commission expires 11-17-62

Mapine Head
Notary Public.

PLUGGING
FILE SEC. 10 T. 20 R. 16W
BOOK PAGE 25 LINE 11

DRILLERS LOG

No. 1 Peterson

CASING RECORD: 8 5/8" @ 1066*
w/500 sx cement

COMPANY: Franco Central Oil Co.

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: March 9, 1959

TOTAL DEPTH: 3790* (-1772)

COMPLETED: March 19, 1959

DESCRIPTION: SW SW NE
10-20S-16W
Pawnee County,
Kansas

ELEVATION: 2015 DF
2018 RB

FORMATION	FROM	TO	REMARKS
Soil and Sand	0	70	
Shale and Shells	70	400	
Blue Shale	400	445	
Sand	445	570	
Shale	570	645	
Red Bed Shale and Shells	645	1046	
Anhydrite	1046	1080	
Shale and Shells	1080	1485	
Lime and Shale	1485	2270	
Shale and Shells	2270	2335	
Shale and Lime	2335	3287	
Lime	3287	3385	
Lime and Shale	3385	3480	
Lime	3480	3775	
Conglomerate	3775	3782	
Arbuckle	3782	3790	

RECEIVED
STATE CORPORATION COMMISSION
MAR 25 1959
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle
George A. Angle

Subscribed and sworn to before me this 23rd day of March, 1959.

Marjorie Head
Notary Public

My Commission Expires: 11-17-62

PLUGGING
FILE SEC. 10 T. 20 R. 16W
BOOK PAGE 25 LINE 11