

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pawnee County. Sec. 9 Twp. 20S Rge. 16 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW

Lease Owner Vickers Explorations, Ltd.

Lease Name Rutherford Well No. 1

Office Address Box 2240 Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed September 29, 1953

Application for plugging filed September 29, 1953

Application for plugging approved September 29, 1953

Plugging commenced September 30, 1953

Plugging completed September 30, 1953

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives Pratt, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3847 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1084'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole w/ mud to 300' Set plug @ 300'. Dump 20 sx cement. Fill w/ mud to 40' set plug @ 40'. Dump 10 sx cement on plug.

10-8-1953

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jayhawk Drilling Co., Inc.

Address Box 2240 Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

John M. Little (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John M. Little


Box 2240 Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1 day of October, 19 53

Allen J. Denton

Notary Public.

My commission expires August 13, 1957.



VICKERS EXPLORATIONS, LTD.

Rutherford, Well #1
NE NE NW Sec. 9-20S-16W
Pawnee County, Kansas

Casing Record:
8 5/8" @ 1084' w/ 450 sx.

Commenced: September 17, 1953
Completed: September 30, 1953

Elevation: 2051 R. B.
D. & A.

LOG

Surface soil & rock	0-40
Shale & Shells	40-130
Shale, Red Beds & Sand	130-360
Shale, Red Beds, Sand streaks	360-440
Sand	440-610
Red Beds, Sand streaks	610-865
Shale	865-1079
Anhydrite	1079-1115
Shale & Shells	1115-1567
Shale, Shells & Salt	1567-1780
Lime & Shale	1780-2250
Lime, Shale & Sand	2250-2310
Lime & Shale	2310-2348
Shale & Lime	2348-2865
Lime & Shale	2865-3135
Lime	3135-3378
Black Shale	3378-3382
Lime	3382-3386
Shale	3386-3395
Lime	3395-3406
Shale	3406-3451
Lime	3451-3457
Shale	3457-3461
Lime & Little Shale	3461-3762
Chert & Shale	3762-3772
Dolomite	3772-3847 T.D.

D.S.T. 3772-3781 open 1/2 hr.
recovered 7' mud, no shows.

D.S.T. 3772-3796 open 1/2 hr.
recovered 7' mud, no shows.

D. S.T. 3796-3847 open 1 hr.
good blow, recovered 840' sulphur
water. Very slight odor at top
F.P. 125#-325# B.H.P. 835# in
15 min.

Sample Tops:

Heebner	3378
Toronto	3395
Douglas	3406
Brown Lime	3451
Lansing	3461
Conglomerate	3762
Arbuckle	3772

I hereby certify that this Log is true and correct to the best of my knowledge and belief.

VICKERS EXPLORATIONS, LTD.

BY James T. Walker

Sworn and subscribed to before me this 6 day of October, 1953.

Allen P. Denton
Notary Public

My Commission Expires August 13, 1957.

