


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rice County, Sec. 28 Twp. 20S Rge. 7 (E) W (W)
Location as "NE/CNW/SE" or footage from lines SW NW SE
Lease Owner Raymond Oil Company, Inc., (Francis M. Raymond)
Lease Name H. Engelland "B" [unclear] Well No. 3
Office Address 410 Fourth National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed October 24 19 56
Application for plugging filed December 2 19 63
Application for plugging approved December 3 19 63
Plugging commenced Dec. 16 19 63
Plugging completed Dec. 20 19 63
Reason for abandonment of well or producing formation No longer commercially
productive

If a producing well is abandoned, date of last production August 6 19 62
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Conglomerate Depth to top 3350 Bottom 3344 Total Depth of Well 3344 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	196'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

*Filled back in the 5 1/2" 10' with gravel and dumped 5 sacks of cement.
Shot pipe off at 2978.90'. Pulled pipe and mudded hole to 200'.
Set rock bridge and dumped 20 sacks of cement. Finished mudding hole
and dumped 10 sacks of cement at base of cellar.*

RECEIVED
STATE CORPORATION COMMISSION

DEC 27 1963

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Bert Self (If additional description is necessary, use BACK of this sheet)
Address Rural Route #4, Hutchinson, Kansas

STATE OF Kans. COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self
R. R. #4, Hutchinson, Kans.

(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of Dec., 19 63

Carol Self
Notary Public.

My commission expires October 18, 1965



Francis M. Raymond
#3 Hattie Engelland "B"

SW NW SE, 28-20S-7W
Rice County, Kansas

Elev: 1645 KB

Comm: 9/11/56
Comp: 10/24/56

Casing: 8-5/8" @ 196'
5-1/2" @ 3338'

Cement: 175 sz, 2CC
50 sz.

Figures Indicate Bottom of Formation

FORMATION	DEPTH
Surface soil-sand	70
Shale & shells	196
Shale, sand, shells	850
Shale & shells	1015
Lime-shale breaks	1280
Lime & shale	1485
Shale & shells	2050
Shale & Lime	2225
Shale & Shells	2375
Lime-shale	2520
Lime	2625
Shale & Lime	2720
Lime-shale-sand	2870
Lime	3205
Lime & shale	3310
Lime-chert-shale	3338
Total Depth	3364-1/2
Tops:	
Heebner	2715
Douglas	2741
Brown Lime	2873
Lansing-Kansas City	2899
Base Kansas City	3243
Shaley Conglomerate	3336
Cherty Conglomerate	3350

RECEIVED
STATE CORPORATION COMMISSION

DEC 5 1963

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I hereby certify that the above information is true and correct to the best of my knowledge.

Francis M. Raymond

Subscribed and sworn to before me this 5 day of November, 1956.

W. J. [Signature]
Notary Public

My commission Expires: 7/8/57