


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rice County, Sec. 29 Twp. 20S Rge. 7W (E) (W)  
Location as "NE/CNW&SW" or footage from lines SW NW NE  
Lease Owner Murfin Drilling Company  
Lease Name Baker Well No. 3  
Office Address 617 Union Center Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced Sept. 24 19 65  
Plugging completed Sept. 30 19 65  
Reason for abandonment of well or producing formation



Locate well correctly on above  
Section Plot

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled back in the 5" with gravel and dumped 5 sacks of cement. Shot pipe off at 2806.95'. Pulled pipe and mudded hole to 200'. Set rockbridge and finished filling surface with ready mix cement.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 11 1965

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Bert Self  
Address Hutchinson, Kans.

STATE OF Kans., COUNTY OF Reno, ss.  
Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self  
R. R. #4, Hutchinson, Kans.  
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of October, 19 65

My commission expires October 18, 1969

Notary Public.

15.159.04221.0000

CHERRY DRILLING CO., INC.  
102 INSURANCE BUILDING  
WICHITA 2, KANSAS

ROTARY DRILLING LOG

Lease: Baker No. 3  
Well No.: 3  
Location: SW NW NE  
Section 29-20S-7W  
Rice County, Kansas  
Elevation: 1629 D.F.  
1626 Gr.  
Well Commenced: 9-11-58  
Well Completed: 9-22-58

Company: Murfin Drilling Co. et al  
Union Center  
Wichita 2, Kansas  
Contractor: Cherry Drilling Co., Inc.  
102 Insurance Building  
Wichita 2, Kansas  
Geologist: W. P. Simmons  
1801 Porter  
Wichita, Kansas  
Surface Pipe: 11 Jts. used 8-5/8" - 231.67  
overall less thds. cemented  
with 175 sx., 27 CC  
Casing: 105 Jts. - 5-1/2" set at 3300',  
3' off bottom with 75 sx. cement.

**RECEIVED**  
STATE CORPORATION COMMISSION  
OCT 11 1965  
CORPORATION COMMISSION  
WICHITA, KANSAS

\*\*\*\*\*

0 - 230	Shale, sand & red bed	2860 - 2940	Lime & shale
230 - 735	Red bed, shale	2940 - 3060	Lime
735 - 990	Shale, salt & shells	3060 - 3303	Lime & shale
990 - 2705	Lime & shale	3303	R. T. D.
2705 - 2860	Sand Lime		

GEOLOGIST'S TOPS

Hebner	2695 (-1063)	Lansing	2880 (-1248)
Toronto	2712 (-1080)	Base of Kansas City	3210 (-1578)
Brown Lima	2850 (-1218)	Cherty Conglomerate	3295 (-1663)
		R. T. D.	3303 (-1671)

The above is a true and correct log to the best of my knowledge.

*Petty P. Pruehl*  
Secretary

Subscribed and sworn to before me this 14th day of October, 1958.

*Donna C. Sisk*  
Donna C. Sisk Notary Public

My Commission Expires: September 5, 1960.