

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Rep.
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rice

County, Sec. 29 Twp. 20S Rge. 7 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE NE SW

Lease Owner Raym ond Oil Company, Inc.

Lease Name Lamberson Well No. 2

Office Address 410 Fourth National Bank Building

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed February 18 19 58

Application for plugging filed December 26 19 63

Application for plugging approved December 27 19 63

Plugging commenced Jan. 4 19 64

Plugging completed 19

Reason for abandonment of well or producing formation Production too low.


If a producing well is abandoned, date of last production June 12 19 63

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom 3317 Total Depth of Well 3317 Feet

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Contains data for casing sizes 8 5/8" and 5 1/2" with depths 228' and 3307'.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled back with gravel and dumped 5 sacks of cement. Shot pipe off at 2805'. Pulled pipe and mudded hole to 200'. Set rock bridge and dumped 20 sacks of cement. Finished mudding hole to 35' and dumped 10 sacks of cement at base of cellar.

RECEIVED STATE CORPORATION COMMISSION

JAN 10 1964 1-10-1964

CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self Casing Pulling Company

Address Rural Route #4, Hutchinson, Kansas


STATE OF Kans., COUNTY OF Reno, ss. Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me, God.

(Signature) Bert Self

R. R. #4, Hutchinson, Kans. (Address)

SUBSCRIBED AND SWORN to before me this 7th day of January, 19 64

My commission expires October 18, 1965 Notary Public.



RAYMOND OIL COMPANY, INC. #2 LAMBERSON
 SE NE SW, 29-20S-7W
 Rice County, Kansas

Contractor: Raymond Oil Co., Inc.

Commenced: 2/10/58
 Completed: 2/18/58 (Rotary)

Elevation: 1631 KB

Casing Record: 8-5/8" @ 228'
 5-1/2" @ 3307'

Cement: 200 sacks
 50 sacks

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Sand & Shale	228
Shale, Shells, Red Bed	630
Shale & Shells	1427
Shale with Shells	1720
Shale with Lime	2000
Shale & Lime	2170
Shale with Shells	2440
Shale & Lime	2690
Shale with Sand	2885
Lime with Shale	2950
Lime & Shale	3040
Lime	3180
Lime & Shale	3317

RECEIVED
 STATE CORPORATION COMMISSION

DEC 27 1963

CONSERVATION DIVISION
 Wichita, Kansas

Tops:

Heebner	2698'
Toronto	2715'
Douglas	2724'
Brown Lime	2850'
Lansing	2878'
Base Kansas City	3214'
Shaley Conglomerate	3294'
Cherty Conglomerate	3301'
Rotary Total Depth	3317'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby certify that the above information is true and correct to the best of my knowledge.

Chas. W. Raymond
 Chas. W. Raymond

Subscribed and sworn to before me this 25th day of February, 1958.

Betty Baker
 Notary Public

My Commission Expires:

2/24/63