

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rice

County. Sec. 29 Twp. 20S Rge. (E) 7 (W)

Location as "NE/CNW/SW" or footage from lines SW SW NE

Lease Owner Raymond Oil Company, Inc.

Lease Name JONES B Well No. 1

Office Address 410 4th National Bank Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed September 16 19 57

Application for plugging filed November 5 19 59

Application for plugging approved November 6 19 59

Plugging commenced DEC. 8 19 59

Plugging completed DEC. 12 19 59

Reason for abandonment of well or producing formation no longer commercially productive

If a producing well is abandoned, date of last production October 10 19 59

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well GILBERT TOMAN

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

SANDED BACK TO 3290 FT. DUMPED 5 SACKS OF CEMENT. SHOP PIPE OFF AT 3029 FT. PULLED PIPE AND MUDDED HOLE TO 225 FT. SET ROCK BRIDGE AND DUMPED 20 SACKS OF CEMENT. FINISHED MUDDING HOLE AND DUMPED 10 SACK OF CEMENT IN TOP OF SURFACE.

STATE CORPORATION COMMISSION
JAN 22 1960
CONSERVATION DIVISION
Wichita, Kansas
1-22-1960

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Bert Self
Address RR #4, Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF RENO, ss.
EMPLOYEE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self
R. R. 4 HUTCHINSON KANS. (Address)

SUBSCRIBED AND SWORN TO before me this 11TH day of DEC. 19 59

Notary Public

My commission expires AUGUST 12-1961

Recorded
mk.

RAYMOND OIL COMPANY, INC. #1 JONES "B"
SW SW NE, 29-20S-7W
Rice County, Kansas

Contractor:
Raymond Oil Company, Inc.

Comm: 8/29/57
Comp: 9/7/57

Elevation: 1632 RB

Casing: 8-5/8@ 236'
5-1/2" @ 3308'

Cement: 200 sx., 2% CC
50 sx.

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Surface Hole	220
Shale & Shells	830
Salt & shale	1040
Lime & Shale	1330
Lime	1460
Shale & Lime	1850
Shale and Shells	2260
Lime & Shale	2790
Shale and Sand	2853
Lime and Shale	3081
Lime	3155
Lime & Shale	3300
Cherty Lime	3309

Tops:

Heebner	2700
Toronto	2718
Douglas	2730
Brown Lime	2853
Lansing	2882
Base Kansas City	3215
Cherty Conglomerate	3300
R. T. D.	3309

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1960
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby certify that the above information is true and correct to the best of my knowledge.

Chas. W. Raymond
Chas. W. Raymond

Subscribed and sworn to before me this 10th day of September, 1957.

Betty Baker
Notary Public

My commission expires: 2/24/60