


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rice County. Sec. 29 Twp. 20S Rge. 7 (E) W (W)

Location as "NE/CNW/SW" or footage from lines \_\_\_\_\_  
Lease Owner Raymond Oil Company, Inc.  
Lease Name Lamberson Well No. 3  
Office Address 410 Fourth National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed 10-6-58 19 64  
Application for plugging filed June 26 19 64  
Application for plugging approved June 30 19 64  
Plugging commenced July 17 19 64  
Plugging completed July 21 19 64  
Reason for abandonment of well or producing formation No longer commercially productive  
If a producing well is abandoned, date of last production July 9 19 64  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	235'	
				5 1/2"	3304'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled back in the pipe with gravel and dumped 5 sacks of cement. Shot pipe off at 2910". Pulled pipe and mudded hole to 200'. Set rock bridge and dumped 20 sacks of cement. Finished mudding hole to 30' and set another rock bridge. Finished mudding and dumped 10 sacks of cement at base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 29 1964  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Bert Self (If additional description is necessary, use BACK of this sheet)  
Address Hutchinson, Kans.

STATE OF Kansas, COUNTY OF Reno, ss. Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self  
R. R. #4, Hutchinson, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of July, 1964

My commission expires Oct. 18, 1965 Notary Public.

Raymond Oil Company, Inc. #3 Lamberson  
 NW SE SW, 29-20S-7W  
 Rice County, Kansas  
 Development Well

Contractor: Raymond Oil Co., Inc.  
 Elevation: 1631 KB

Commenced: 9/29/58  
 Completed: 10/6/58 (Rotary)

Casing Record  
 8-5/8" @ 235' w/200 sacks  
 5-1/2" @ 3304' w/79 sacks

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Surface Hole	235
Shale, Shells & Red Bed	470
Shale & Shells	930
Lime & Shale	2680
Lime	2730
Lime & Shale	2746
Sand	2760
Shale	2765
Sand	2780
Shale	2859
Limestone <sup>29</sup>	2900
Lime with shale	3045
Lime	3300
Chert	3315

**RECEIVED**  
 STATE CORPORATION COMMISSION

APR 3 1964

CONSERVATION DIVISION  
 Wichita, Kansas

Tops:

Heebner	2701
Toronto	2724
Douglas	2729
Douglas Sand	2746
Brown Lime	2859
Lansing	2883
Base of Kansas City	3214
Cherty Conglomerate	3300
RTD	3315


STATE OF KANSAS        )  
                                   ) SS  
 COUNTY OF SEDGWICK )

I hereby certify that the above information is true and correct to the best of my knowledge.

*Lloyd M. Greenstreet*  
 Lloyd M. Greenstreet

Subscribed and sworn to before me this 28th day of October, 1958

My commission expires: 2/24/60



*Betty Baker*  
 Betty Baker  
 Notary Public