


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rice County, Sec. 26 Twp. 20S Rge. (E) 7 (W)  
Location as "NE/CNW/SW" or footage from lines SE SE NE/4  
Lease Owner Richard & Byram  
Lease Name Leonora Baker Well No. 1  
Office Address 906 Grand Avenue, Kansas City 6, Missouri  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 31, 1956  
Application for plugging filed December 31, 1956  
Application for plugging approved 19  
Plugging commenced December 31, 1956  
Plugging completed December 31, 1956  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3415 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Gummed pits, lowered suction, and loaded hole. Layed down drill pipe and set plug at 190' with 15 sacks of cement through 6 joints of drill pipe. Filled up surface pipe to 20' and set plug with 5 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor  
Address

STATE OF KANSAS, COUNTY OF Sedgwick, ss.  
Raymond Oil Company, Inc., Contractor (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Raymond M. Shandor  
209 Petroleum Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of December, 1956.

May Ellen Cummins  
RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public.

My commission expires 7/8/56

PLUGGING  
FILE SEC. 26 T. 20 R. 2W.  
BOOK PAGE 129 LINE 34

JAN 2 1957 1-2-1957  
CONSERVATION DIVISION  
Wichita, Kansas

RICHARD & BYRAM #1 LEONORA BAKER  
 SE SE NE, 26-20S-7W  
 RICE COUNTY, KANSAS

Contractor: Raymond Oil Co., Inc.

Comm: 12-17-56  
 Comp: 12-31-56

Elev: 1673 DF  
 1676 KB

Casing: 8-5/8" @ 197

Cement: 150 sacks, 2 CC

Figures Indicate Bottom of Formation

FORMATION	DEPTH
Shale & Shells	1220
Shale & Lime	1310
Lime & shale - sandy	1430
Lime with shale	1957
Shale & Shells	2500
Shale & Sand	2650
Lime and shale	2729
Shale	2734
Lime and Shale	2765
Sand	2875
Shale & Sand	3045
Lime	3119
Lime & Sand	3175
Shale & Lime	3270
Lime and Shale	3353
Lime & Chert	3370
Cherty Lime	3372
Chert with Lime	3395
Lime and Shale	3415

Tops:

Heebner	2708
Douglas	2754
Brown Lime	2870
Lansing-Kansas City	2899
Cherty Conglomerate	3364
Mississippian Chert	3377
Kinderhook	3407
Rotary Total Depth	3415
D & A	

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

I hereby certify that the above information is true and correct to the best of my knowledge.

*Lloyd M. Greenstreet*

Subscribed and sworn to before me this 31st day of December, 1956.

*Mary Ellen Cummins*  
 Notary Public

My Commission Expires 7/8/56

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 2 1957

CONSERVATION DIVISION  
 Wichita, Kan.

PLUGGING			
FILE	SEC 26	T. 20	R. 7W
BOOK	PAGE 229	LINE	34