

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR


FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
300 Bittling Building  
Wichita, Kansas

Rice County. Sec. 26 Twp. 20 Rge. 7 (W)

Location as "NE1/4NW1/4SW1/4" or footage from lines SE SE SE  
Lease Owner Keyes Drilling Co. et al  
Lease Name Tobias Well No. 1  
Office Address Ellinwood, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 27, 1947 19  
Application for plugging filed Aug. 9, 1947 19  
Application for plugging approved Aug. 9, 1947 19  
Plugging commenced August 11, 1947 19  
Plugging completed August 14, 1947 19  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production - - - - - 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes


Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation - - - - - Depth to top - - - - - Bottom - - - - - Total Depth of Well 3399 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface pipe	160'	0	160	8 5/8	160	none
Oil String	3369'	0	3369	5 1/2	3369	2621

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from - - - - - feet to - - - - - feet for each plug set.

Filled with crushed rock from 3399 to 3360; cemented with 6 sacks at 3360; filled with heavy mud from 3360 to 160; set rock bridge from 160 to 150 and cemented with 10 sacks at 150; set rock bridge from 25 to 15 and cemented on top of rock bridge from 15 feet to top of hole.



8-27-1947

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to G. W. Keyes Drilling Company  
Address Ellinwood, Kansas

STATE OF Kansas COUNTY OF Barton ss.  
I, G. W. Keyes, Part Owner (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. W. Keyes  
Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of August, 1947  
George A. Meyer  
Notary Public.

My commission expires Feb. 10, 1951

**PLUGGING**  
FILE SEC 26 T 20 R 7W  
BOOK PAGE 26 PAGE 42

G. W. Keyes Drilling Co., et al, Owners - Tobias No. 1  
 Cen SE/4 SE/4 SE/4 Section 26, Township 20S, Range 7 W,  
 Rice County, Kansas

Elevation	1684	Figures indicate bottom of formation	0 to 103 sand
Pipe Record			130 shale and shells
8 5/8" set at 160' Cemented with 100 sacks			163 red bed and shells
5 1/2" set at 3369' Cemented with 50 sacks			458 red bed and shale
Tops corrected 3' to derrick floor			485 anhydrite
Heebner shale	2715		810 shale and shells
Base Oread	2748		1110 shale, shells & salt
Brown lime	2880		1165 shale and shells
Lansing(buff)	2906		1265 lime
Chert Congl.	3369		1525 lime and shale
Miss Chert	3375		1745 lime
Rotary commenced	6-28-47		2430 shale and shells
Rotary completed	7-10-47		2615 lime and shale
Cable Tools Commenced	7-19-47		2750 lime
Cable Tools completed	7-27-47		2820 sandy shale
			2920 shale and lime
			3215 lime
			3290 shale and shells
			3372 shale
			3378 conglomerate
			3381 Miss. Chat
			3381 Total Rotary Depth

CABLE TOOL WORK

Moved in cable tools, drilled cement, cleaned out to total depth and drilled deeper.

3399 chat  
 3399 Total Depth D&A

STATE OF KANSAS )  
 COUNTY OF BARTON ) SS

I, W. F. Banks, Production Superintendent for Keyes Drilling Co. et al, Owners of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well as filed, and that the same are true and correct.

Subscribed and Sworn to before me this 5th day of August, 1947

*W. F. Banks*  
 \_\_\_\_\_  
*George A. Meyer*  
 \_\_\_\_\_  
 Notary Public

My commission expires Feb. 10, 1951

G. W. Keyes Drilling Co., et al, Owners - Tobias No. 1  
 Cen SE/4 SE/4 SE/4 Section 26, Township 20S, Range 7 W,  
 Rice County, Kansas

Elevation	1684	0	to	103 sand
Pipe Record				130 shale and shells
				163 red bed and shells
				458 red bed and shale
8 5/8" set at 160' Cemented with 100 sacks				486 anhydrite
5 1/2" set at 3369' Cemented with 50 sacks				810 shale and shells
Tops corrected 5' to derrick floor				1110 shale, shells & salt
Heebnor shale	2715			1165 shale and shells
Base Oread	2748			1265 lime
Brown lime	2880			1528 lime and shale
Lansing (buff)	2906			1745 lime
Chert Congl.	3369			2430 shale and shells
Miss Chert	3375			2615 lime and shale
				2750 lime
				2820 sandy shale
Rotary commenced	6-28-47			2920 shale and lime
Rotary completed	7-10-47			3215 lime
				3290 shale and shells
Cable Tools Commenced	7-19-47			3372 shale
Cable Tools completed	7-27-47			3378 conglomerate
				3381 Miss. Chat
				3381 Total Rotary Depth

## CABLE TOOL WORK

Moved in cable tools, drilled cement, cleaned out  
 to total depth and drilled deeper.

3399 chat  
 3399 Total Depth D&A

STATE OF KANSAS )  
 COUNTY OF BARTON ) SS

I, W. F. Banks, Production Superintendent for Keyes Drilling Co. et al, Owners of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well as filed, and that the same are true and correct.

*W. F. Banks*

Subscribed and Sworn to before me this 5th day of August, 1947.

*Charles Meyer*  
 Notary Public

My commission expires Feb. 10, 1951

