

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Rice County. Sec. 26 Twp. 20S Rge. (E) 7 (W)
Location as "NE/CNW%SW%" or footage from lines SE SW
Lease Owner Jayhawk Oil Co.
Lease Name Tobias Well No. 1
Office Address 103 One Twenty Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed August 21 19 68
Application for plugging filed Sept. 23 19 68
Application for plugging approved 19
Plugging commenced Sept. 30 19 68
Plugging completed October 4 19 68
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Tolman
Producing formation none Depth to top Bottom Total Depth of Well 3403 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	170'	none
				5-1/2"	3393	2854'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

5 1/2" casing @ 3393' w/75 sks.

Bridge plug @ 3380'. Sanded hole to 3360'. 5 sks of cement @ 3360'. Shot pipe

@ 2922' and 2826'. Pulled 2854' 5 1/2" casing. Mudded hole from 3335 to 210'.

Rock bridge 210' to 200'. 25 sks cement @ 200'. Mud to 35'. 10 sks cement

35' to 4' below ground level.

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Braden-Deem, Inc.
Address 210 One Twenty Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Doy C. Deem (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
210 One Twenty Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11 day of October, 1968

My commission expires March 21, 1970

Notary Public.

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

15.159.20147.0000

COMPANY Jayhawk Oil Co.

SEC. 26 T. 20S. 7W
LOC. SE SW

FARM Tobias


NO. 1

TOTAL DEPTH 3,394'
COMM. August 3, 1968
SHOT OR TREATED
CONTRACTOR H-30, INC.
ISSUED

COMP. August 10, 1968

COUNTY Rice

KANSAS



CASING
20 10 -5/8" 169' cemented w/190 sx cement ELEVATION 1698 KB
15 B
12 6 -1/2" 3393' cemented w/75 sx cement PRODUCTION
13 5

FIGURES INDICATE BOTTOM OF FORMATIONS

Clay	40
Sand	70
Shale	755
Salt & Shale	980
Shale & Shells	1335
Shale & Lime	1500
Lime	1725
Lime & Shale	2795
Shale & Lime	2925
Lime	3394
Rotary Total	
Depth	3394

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1968
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo E. Romer
Arlo E. Romer

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 15th day of August, 1968.

Martha Hartpence
Martha Hartpence - Notary Public

My Commission Expires:

April 21, 1971