


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 N. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rice County, Sec. 25 Twp. 20S Rge. 7 (E) W (W)
Location as "NE/CNW/SW" or footage from lines E/2 NE SW
Lease Owner Schreiner Petroleum Co.
Lease Name Keimple Well No. 1
Office Address 548 Petroleum Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-16, 67
Application for plugging filed 6-16, 67
Application for plugging approved 6-16, 67
Plugging commenced 6-16, 67
Plugging completed 6-16, 67
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3428 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		RECEIVED STATE CORPORATION COMMISSION JUN 29 1967 CONSERVATION DIVISION Wichita, Kansas		8 5/8	207'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with heavy rotary mud
200 ft. Bridge at 200 ft. with
hulls and 25 sacks cement. Hole filled
with mud to 40' Bridge at 40 ft. with
hulls and 10 sacks cement. Rathole
capped with 2 sacks cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor WHITE & ELLIS DRILLING, INC. License #209
Address Box 448, El Dorado, Kansas 67042

STATE OF Kansas, COUNTY OF Butler, ss.
Howard E. Russell, an employee of contractor (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Howard E. Russell
Box 448, El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of June, 1967

Ernest J. [Signature]
Notary Public.

My commission expires May 21, 1968

CASING RECORD

8 5/8

207' Cemented
w/150 sacks

T. D.

3428'

KELLY BUSHING MEASUREMENT 5' ABOVE GROUND LEVEL.

<u>FORMATION</u>	<u>DEPTH</u>
Cellar	0-7
Sand, Lime & Shale	207
Red Rock	400
Shale	1000'
Lime & Shale	1580
Lime	1760
Shale & Lime	2155
Lime & Shale	2530
Lime	2730
Shale	2795
Lime	2815
Lime & Shale	2897
Lime	3315
Lime & Shale	3370
Conglomerate	3404
Lime	3428

TOPS

Heebner	2706
Douglas	2768
Kansas City	2894
Mississippi	3404

15.159.20044.0000

Location: E/2 NE SW
 Section: 25-20S-7W
 Rice County, Kansas
 Farm: Keimple #1
 Well Owner: Schreiner Petro. Co.
 Contractor: WHITE & ELLIS
 DRILLING, INC.
 Commenced: 6-9-67
 Completed: 6-16-67
 Elevation: 1668' K.B.

Dry Hole, Plugged
& Abandoned