


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Rice County. Sec. 18 Twp. 20S Rge. 7W (E) (W)  
Location as "NE/CNW%SW%" or footage from lines SW SW SE  
Lease Owner Cherry Drilling Co., Inc.  
Lease Name SHEPHERD Well No. 1  
Office Address 102 Insurance Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 15, 1957  
Application for plugging filed August 15, 1957  
Application for plugging approved August 15, 1957  
Plugging commenced August 15, 1957  
Plugging completed August 15, 1957  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3547 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Gunned pits & raise weight mud - circulated & brought heavy mud around. Layed down drill pipe & filled hole with heavy mud to 225'. Built solid rock bridge to hold weight of drill pipe to 212'. Ran 15 sx. cement through 7 joints drill pipe. Set Top Bridge @ 35' with 5 sx. cement.

8-21-1957

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Cherry Drilling Co., Inc.  
Address 102 Insurance Building

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Franklin Hiebert (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Franklin Hiebert  
102 Insurance Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of August, 1957

My commission expires April 22, 1959 Betty Brandt Notary Public.

PLUGGING  
FILE SEC 18 T. 20 R. 7W  
BOOK PAGE 38 LINE 5

CHERRY DRILLING CO., INC.  
102 INSURANCE BUILDING  
WICHITA 2, KANSAS

LEASE: Shepherd	Company	Cherry Drilling Co., Inc. 102 Insurance Building Wichita 2, Kansas
Well No. 1		
Location: SW SW SE Sec. 18-20S-7W Rice County, Kansas	Contractor	Cherry Drilling Co., Inc.
Elevation: 1643 D. F. 1646 K. B.	Geologist	W. P. Simmons 303 Farm & Bank Life Bldg. Wichita, Kansas
Well Commenced: 8-6-57	Surface Pipe	11 Jts. used surface pipe cemented with 175 sx. reg. cement, 2% CC
Well Completed: 8-15-57		

CASING: D & A

\*\*\*\*\*

0- 225	Sand, red beds, shale
225- 700	Red beds, shale
700-1160	Lime & shale
1160-1640	Lime & shale
1640-2075	Shale & lime
2075-2405	Lime & shale
2405-2625	Lime
2625-2730	Lime & sand
2730-2890	Sand & lime
2890-3265	Lime
3265-3315	Lime & shale, chert
3315-3485	Lime & shale
3485-3547	Lime & shale & sand
3547	R. T. D.

PLUGGING  
FILE SEC 18 T 20 R 7W  
BOOK PAGE 38 LINE 5

CONSULTING ENGINEER  
Wichita, Kansas  
COMMISSION

GEOLOGIST'S TOPS

Heebner	2712	Conglomerate	3272
Toronto	2735	Kniderhook	3298
Douglas	2760	Viola	3502
Brown Lime	2860	Simpson	3530
Lansing Kansas City	2887	T. D.	3547
Base Kansas City	3222		

The above is a true and correct log to the best of my knowledge.

Subscribed and sworn to before me on this 20th day of August, 1957.

My Commission expires April 22, 1959.

Betty Brandt Notary Public