



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 2 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Poe of Lario Oil & Gas Co. has this  
date requested permission to plug the following described well:

Mr. Poe guarantees payment of the plugging fee.

Operator's full Name: Lario Oil & Gas Co.

Complete Address: 301 S. Market Wichita, Kansas

Lease Name: Steffen Well No. 6

Location: NW SW Sec. 29 Twp. 20 Rge. (E)(W) 20

County: Pawnee Total Depth 4353' Oil Well

Gas Well      Input Well      SWD Well      D & A XX Lost Hole     

Mr. Poe was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 600' and displace  
50 sk cmt thru drill pipe. Heavy mud to 360' set cementing plug and  
displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

[Signature]  
Conservation Division Agent