



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 18 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Kohlrus of Birmingham & Bartlett Drlg. has this date requested permission to plug the following described well:

Mr. Kohlrus guarantees payment of the plugging fee.

Operator's full Name: Birmingham & Bartlett Drilling Co.

Complete Address: 300 Kaufman Bldg. Wichita, Kansas

Lease Name: Tombaugh Well No. 2

Location: 150' NW C NE SW Sec. 31 Twp. 20 Rge. 20 (E)(W) X

County Pawnee Total Depth 4387' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Kohlrus was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace 25 sc cement thru drill pipe. Heavy mud to 250' set cementing plug and displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug. 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole with 2 sc cement.

Very truly yours,

Leo F. Messer
Conservation Division Agent