

State of Kansas



15.145.30104.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Lacy of Beardmore Drilling Co. has this date requested permission to plug the following described well:

Mr. Lacy guarantees payment of the plugging fee.

Operator's full Name: Beardmore Drilling Co.

Complete Address: 700- One Twenty Bldg., Wichita, Kansas

Lease Name: Miller "F" Well No. 1

Location: NW NW Sec. 31 Twp. 20 Rge. 20 (E) (W) X

County Pawnee Total Depth 4391 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Lacy was instructed to plug the well as follows:

Gun pits, Circulate heavy mud, set cementing plug at 540 Ft.  
and displace 25 sc cement thru drill pipe. Heavy mud to 300 Ft. set  
cementing plug and displace 20 sc cement thru drill pipe. Heavy mud  
to 40 Ft. set cementing plug, 1/3 sc hulls and 10 sc cement to base  
of celler. Plug rat hole with 2 sc cement.

Very truly yours,

Conservation Division Agent