

State of Kansas



15.145.20581.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. French of Pickrell Drlg. has this

date requested permission to plug the following described well:

Mr. French guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drlg. Co.,

Complete Address: 205 Litwin Bldg., Wichita, Ks.

Lease Name: Miller "F" Well No. 1

Location: C NE NW Sec. 31 Twp. 20 Rge. (E)(W) 20

County: Pawnee Total Depth 4390' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. French was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 550' thru drill
pipe. Heavy mud to 200' set 25 sk cmt plug thru drill pipe. Heavy
mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1979

Very truly yours,
CONSERVATION DIVISION
Wichita, Kansas

Geo Massey
Conservation Division Agent