



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 26 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Rowe of Slawson Drlg. has this

date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 408 One Twenty Bldg., Wichita, Ks.

Lease Name: Petersilie "A" Well No. 3

Location: SE NW SW Sec. 21 Twp. 20 Rge. (E)(W) 23

County: Ness Total Depth 4387' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Rowe was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 550' and displace
50 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug,
1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo F. Massey
Conservation Division Agent