

State of Kansas



FORM - CP-2
Rev. 9-8-64

15.159.02601.0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B HARVEY Secretary
E. EDWARD JOHNSON Gen Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

December 11, 1965

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bert Self of Self Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company

Complete Address: 617 Union Center, Wichita, Kansas

Lease Name: Beal Well No. 5

Location: NW NW SW Sec. 28 Twp. 20 Rge. 7 (E) (W) X

County Rice Total Depth 3314' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3300' and cement with 5 sacks.

Fill hole with mud to 210'. Set rock bridge from 210' to

195' and cement hole to base of cellar with 2½ yards ready-

mix cement.

Very truly yours,


Conservation Division Agent