

KANSAS

J
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Company

Complete Address 200 W. Douglas Wichita, Kansas 67202

Lease Name Petersilie Well No. 2

Location C SW NE Sec. 21 Twp. 20 Rge. (E) (W) 23

County Ness Total Depth 4385'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 6 P Day 23 Month 2 Year 1972

The above well was plugged as follows:

Total Depth 4385' 8 5/8 csg set at 433' cwc

5 1/2 csg set at 4381' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (4350-4385) dumped 5 sk cmt W/dump bailer. (4315-4350)

Cutoff and recovered 2500' of 5 1/2 csg.

Pumped down 8 5/8 csg with 18 sk gel & water W/300 lbs hulls(680-1450) released

8 5/8 plug and pumped 80 sk 50-50 poz cmt W/6% gel (360-680) 7 sk gel & water

(80-360) 20 sk 50-50 poz cmt W/6% gel. (0-80)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Leo J. M...*
Well Plugging Supervisor

DATE 2-28-72

INV. NO. 5241-W