

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 26 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Donald C. Slawson

Complete Address 408 One Twenty Bldg., Wichita, Kansas

Lease Name Petersilie "A" Well No. 3

Location SE NW SW Sec. 21 Twp. 20 Rge. (E) (W) 23

County Ness Total Depth 4387'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor        Co. Tools       

Address        License No.       

Operation Completed: Hour 7 A Day 20 Month 11 Year 1973

The above well was plugged as follows:

RTD 4387' 8 5/8 csg set at 427' cwc

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 50 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/29/73

INV. NO. 8219-W

Signed: Bob F. Truesdell  
Well Plugging Supervisor