

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 16 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Vernon Faulconer

Complete Address: 336 Union Center Bldg. Wichita, Kansas 67530

Lease Name Baker Well No. # 1

Location SE SE SE Sec. 29 Twp. 20 Rge. 7 (E) (W)

County Rice Total Depth 3325'

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Art Lamb Casing Pulling

Address: Hutchinson, Kansas License No. 440

Operation Completed: Hour 11 AM Day 13 Month 9 Year 68

The Above well was plugged as follows:

8 5/8"-210'-Circulated w/cement. 5 1/2"-3303'-Cemented. Sand hole to 3290'.

5 Sax.cement 3290' to 3250'. Mud 3250' to 270'. Bridge 210' to 200'.

25 Sax.cement 200' to 125'. Mud 125' to 40'. Bridge 40' to 30'.

10 Sax.cement 30' to 0. Pulled 2885'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/16/68  
INV. NO. 8465-4

Signed: [Signature]  
Well Plugging Supervisor