

State of Kansas



FORM - CP-2  
Rev. 6-26-62

15.159.04218.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

December 17, 1963

RECEIVED  
STATE CORPORATION COMMISSION

DEC 26 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Bert Self of Bert Self Casing Pulling Co has this date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Inc.

Complete Address: 410 4th Nat'l Bank Bldg., Wichita, Kansas

Lease Name: H. Engelland "B" Well No. 3

Location: SW NW SE Sec. 28 Twp. 20 Rge. 7 (E) (W) X

County Rice Total Depth 3344' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3325' and cement with 5 sacks.

Fill hole with mud to 210'. Set rock bridge from 210' to 200' and cement with 20 sacks. Fill hole with mud to 40'.

Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,