

State of Kansas



FORM - CP-2
Rev. 6-26-62

15-159-04223-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

December 31, 1963 RECEIVED
STATE CORPORATION COMMISSION

JAN 14 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Bert Self of Bert Self Casing Pulling Cchas this date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Inc.

Complete Address: 410 Fourth Nat'l Bank Bldg., Wichita, Kansas

Lease Name: Lamberson Well No. 1

Location: NE NE SW Sec. 29 Twp. 20 Rge. 7 (E) (W) X

County Rice Total Depth 3315' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3300' and cement with 5 sacks.

Fill hole with mud to 210'. Set rock bridge from 210' to

200' and cement hole with 20 sacks. Fill hole with mud to

40'. Set rock bridge from 40' to 30' and cap hole with 10

sacks cement.

Very truly yours,