

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

July 16, 1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1964

Dear Sir:

CONSERVATION DIVISION
Wichita, Kansas

Mr. Bert Self of Bert Self Casing Pulling has this

date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Inc.

Complete Address: 410 Fourth Nat'l Bank Bldg., Wichita, Kansas

Lease Name: Lamberson Well No. 3

Location: NW SE SW Sec. 29 Twp. 20 Rge. 7 (E) (W) X

County Rice Total Depth 3315' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 3290' and cement with 5 sacks.

Fill hole with mud to 230'. Set rock bridge from 230'
to 220' and cement hole with 20 sacks. Fill hole with
mud to 40'. Set rock bridge from 40' to 30' and cap hole
with 10 sacks cement.

Very truly yours,

Alfred J. Leonard
Conservation Division Agent