



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

September 28, 1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 1 1 1968
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Orville Powell of Braden-Deem, Inc. has this

date requested permission to plug the following described well:

Mr. Powell guarantees payment of the plugging fee.

Operator's full Name: Jayhawk Oil Company

Complete Address: 103 One Twenty Bldg., Wichita, Kansas 67202

Lease Name: Tobias Well No. 1

Location: SE SW Sec. 26 Twp. 20 Rge. 7 (E) (W) X

County: Rice Total Depth 3405' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Powell was instructed to plug the well as follows:

Fill hole with sand to 3360' and cement with 5 sacks.

Fill hole with mud to 210'. Set rock bridge from 210' to 200' and

cement with 25 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent