

State of Kansas



15.159.20044.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

June 16, 1967

RECEIVED  
JUN 23 1967  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Thompson of White & Ellis Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Schreiner Petroleum Co.

Complete Address: 501 Petroleum Bldg., Wichita, Kansas

Lease Name: Kimple Well No. 1

Location: C EL NE SW Sec. 25 Twp. 20 Rge. 7 (E) (W) X

County Rice Total Depth 3424' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Thompson was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/4 sack hulls to 200' and  
cement hole with 25 sacks through drill pipe. Fill hole with mud to  
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks  
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent