

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-23031-00-00
Spot: NWSWNESE Sec/Twnshp/Rge: 12-10S-20W
1665 feet from S Section Line, 1215 feet from E Section Line
Lease Name: EARL SUTOR Well #: 10
County: ROOKS Total Vertical Depth: 3935 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3933		200 SX
SURF	8.625	1282		475 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/18/2017 10:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: DYLAN KLAUS Company: VESS OIL CORPORATION DBA Phone: (316) 518-7692

Proposed Plugging Method: 2010: Squeeze from 1300' to surface with 235 sx. Cwc.
Production perforations: 3767' - 3773'.
Tight casing spots at 3627' and 3697'.
Surface pipe covers Dakota.
Anhydrite at 1636'. Need to perforate 2 holes.
Ordered 300 sx 60/40 pomix 4% gel cement, 500 # hulls and 1600 # gel spacer.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/18/2017 2:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perf Tech: shot 2 holes at 1630'. Ran tubing to 3600'. Basic Energy Services, LP pumped 1600 # gel spacer, followed by 50 sx cement w/200 # hulls mixed in. Pulled tubing to 1677' and pumped 160 sx cement w/200 # hulls. Cement circulated. PTOH. Hooked up to casing and pumped 30 sx cement. Maximum pressure 300 psi. Shut in pressure 300 psi. Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3767	3773		

INVOICED
JAN 30 2018

Remarks:

Plugged through: TBG

District: 04

Signed



KCC WICHITA

(TECHNICIAN)

CM

JAN 02 2018

RECEIVED

DEC 22 2017

Form CP-2/3