

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-20922-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 6-17S-29W  
3034 feet from S Section Line, 1338 feet from E Section Line  
Lease Name: DIREEN - F Well #: 1  
County: LANE Total Vertical Depth: 4626 feet

Operator License No.: 31627  
Op Name: WHITETAIL CRUDE, INC  
Address: PO BOX 544 14216 N US HWY 283  
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4624	816	WITH 150 SX CMT
SURF	8.625	347		WITH 325 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/13/2017 9:30 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: SAND PERFS TO 4050' WITH 4 SX CMT. TEST CASING. PERFORATE AT 2250'. PUMP 50 SX CMT WITH 100# HULLS IN LAST 25 SX CMT. PERFORATE AT 1260'. PUMP 50 SX CMT WITH 100# HULLS IN LAST 25 THROUGH TBG. CUT CASING AT 600' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/14/2017 1:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

12/13/17: SANDED PERFS TO 4050' WITH 4 SX CMT. PERFORATE AT 2250'. RAN TBG & PUMPED 50 SX CMT IN AND OUT PLUG WITH 100# HULLS IN LAST 25 SX CMT. PULLED TBG. CUT CASING AT 1258'. COULD NOT PULL CASING SO PUMPED ANOTHER 50 SX CMT IN & OUT PLUG WITH 100# HULLS IN LAST 25 SX CMT. CUT CASING AT 816'. PULLED TO 600' & PUMPED 200 SX CMT. DID NOT CIRCULATE. SDON. 12/14/17: TAGGED CMT WITH TBG AT 360'. CIRCULATED TO SURFACE WITH 60 SX CMT. PULLED TBG. TOPPED OFF WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4113	4200		

INVOICED  
12/14/17

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
DEC 27 2017

[Signature]

JA