

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 266 N. Main St., Ste. 220  
 Wichita, KS 67202-1513

API Well Number: 15-187-20984-00-00  
 Spot: NWSENE SW Sec/Twnshp/Rge: 36-29S-41W  
1782 feet from S Section Line, 2114 feet from W Section Line  
 Lease Name: MARTIN Well #: 1  
 County: STANTON Total Vertical Depth: 5688 feet

Operator License No.: 33856  
 Op Name: WHITE EXPLORATION, INC.  
 Address: 1635 N WATERFRONT PKWY STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5408		WITH 2 SX CMT
CIBP		5600		
PROD	5.5	5684	1810	WITH 150 SX CMT
SURF	8.625	1656		WITH 650 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/08/2017 9:00 AM  
 Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
 Proposal Rcvd. from: TERRY BAIRD Company: WHITE EXPLORATION Phone: (316) 641-8906

Proposed Plugging Method: SET CIBP @ 5410' WITH 2 SX CMT. PLUG AT 1710' WITH 12 SX GEL & 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEN SCOFIELD Witness Type: COMPLETE (100%)  
 Date/Time Plugging Completed: 12/08/2017 1:30 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

CIBP @ 5408' WITH 2 SX CMT. 1ST PLUG AT 1694' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 603' WITH 40 SX CMT. 3RD PLUG AT 38' WITH 20 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5604	5608		
5456	5476		

INVOICED  
 JAN 20 2018

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

*Heith Walsh*  
 SA (TECHNICIAN)

RECEIVED  
 DEC 12 2017  
 KCC DODGE CITY