

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-25120-00-00
Spot: W2E2W2W2 Sec/Twnshp/Rge: 1-29S-14E
2640 feet from S Section Line, 4425 feet from E Section Line
Lease Name: PIERPOINT FARMS Well #: 38
County: WILSON Total Vertical Depth: 1150 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.375	1150		98 SX
SURF	7	25		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/17/2017 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS LLC Phone: (620) 325-4344

Proposed Plugging Method: Hook to well at surface and establish circulation then pump 15 ppg cement until well pressures up and shut in. Bleed pressure off the next day and cut below plow depth.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 11/17/2017 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:
The wellhead was connected to and circulation established by pumping 5 bbls of fresh water. The well was then pumped full of cement that contained cottonseed hulls by using the squeeze method. The well was shut in with 750 psi. The next day the well was cut off below plow depth and the location restored. A total of 38 sacks of portland cement were used to plug the well.

Perfs:

RECEIVED
KCC DIST # 3
JAN 16 2018
CHANUTE, KS
AD

INVOICED
JAN 30 2018

Remarks:
Plugged through: CSG

District: 03 Signed Alan Dunning
(TECHNICIAN)