

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-25080-00-00
Spot: E2SESWNW Sec/Twnshp/Rge: 1-29S-14E
2970 feet from S Section Line, 4095 feet from E Section Line
Lease Name: PIERPOINT FARMS Well #: 34
County: WILSON Total Vertical Depth: 1150 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	1103		120 SX
SURF	7	40		12 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/16/2017 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Revd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS LLC Phone: (620) 325-4344

Proposed Plugging Method: Hook onto wellhead establish circulation and start pumping cement until well pressures up. Return the following day and release pressure then cut well off below plow depth.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 11/16/2017 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

The well head was connected to and circulation established by pumping 5.5 bbls of water. The well was then pumped full of cement that contained cottonseed hulls by using the squeeze method. The well was shut in with 850 psi. The wellhead was cut off below plow depth the next day and the location restored. A total of 42 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
1054	1076		

RECEIVED
KCC DIST # 3
JAN 16 2018
CHANUTE, KS

AD

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)