

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-24304-00-00  
Spot: NWNESENW Sec/Twnshp/Rge: 1-29S-14E  
3765 feet from S Section Line, 3105 feet from E Section Line  
Lease Name: PIERPOINT FARMS Well #: 19  
County: WILSON Total Vertical Depth: 1150 feet

Operator License No.: 34697  
Op Name: WILSON COUNTY HOLDINGS LLC  
Address: 1135 N. 15TH ST.  
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.375	1100		105 SX
SURF	7	25		10 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/17/2017 12:00 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS LLC Phone: (620) 325-4344

Proposed Plugging Method: Hooked to well at surface establish circulation then pump 15ppg cement until well pressures up and shut in. Cut well off below plow depth the next day.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE  
Date/Time Plugging Completed: 11/17/2017 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

The wellhead was connected to and circulation established by pumping 6 bbls of water. The well was then pumped full of cement that contained cottonseed hulls by using the squeeze method. The well was shut in with 750 psi. The wellhead was cut off below plow depth the next day and the location restored. A total of 38 sacks of portland cement were used to plug well.

Perfs:

RECEIVED  
KCC DIST # 3  
JAN 16 2018  
CHANUTE, KS

AD  
INVOICED  
JAN 30 2018

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning  
(TECHNICIAN)