

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21835-00-00
Spot: E2NENENW Sec/Twnshp/Rge: 23-33S-8W
330 feet from N Section Line, 2615 feet from W Section Line
Lease Name: SCHUTTE TRUST 3308 Well #: 23-1
County: HARPER Total Vertical Depth: 60 feet

Operator License No.: 35053
Op Name: TAPSTONE ENERGY, LLC
Address: PO BOX 1608
OKLAHOMA CITY, OK 73101

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	18	60		30 sx cement
PROD	0	0		0 SX
SURF	0	0		0 SX

Well Type: SWD UIC Docket No: _____ Date/Time to Plug: 12/27/2017 12:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: LARRY SETTLE Company: TAPSTONE Phone: (620) 896-7200

Proposed Plugging Method: MIRU WSU, PU Swivel, PU 8-1/2 bit and three 4-1/2 drill collars, wash down conductor to 60', circulate 8 bpm and cleanout rock and dirt, Use hydro-vac truck to take returns and suck out mouse hole to 45'. RU cementers, RIH with 2-7/8" tbg, circulate 90 sks class H cement to surface, fill mouse hole with 32 sks cement. RDMO WSU and cementers.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/28/2017 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

Remove standing fluid from inside of conductor and mousehole. Filled both with 7 total yards of Redi Mix.

INVOICED
JAN 30 2018

Remarks: ANDALE REDI MIX DENIED TA

Plugged through:

District: 02

Signed _____

(TECHNICIAN)

15K