

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-21833-01-00  
Spot: W2NWNWNE Sec/Twnshp/Rge: 23-33S-8W  
330 feet from N Section Line, 2605 feet from E Section Line  
Lease Name: SCHUTTE TRUST 3308 Well #: 23-1H  
County: HARPER Total Vertical Depth: 60 feet

Operator License No.: <u>35053</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>TAPSTONE ENERGY, LLC</u>	COND	18	60		30 sx cement
Address: <u>PO BOX 1608</u>	PROD	0	0		0 SX
<u>OKLAHOMA CITY, OK 73101</u>	SURF	0	0		0 SX

Well Type: SWD UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/27/2017 12:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: LARRY SETTLE Company: TAPSTONE Phone: (620) 896-7200

Proposed Plugging Method: MIRU WSU, PU Swivel, PU 8-1/2 bit and three 4-1/2 drill collars, wash down conductor to 60', circulate 8 bpm and cleanout rock and dirt, Use hydro-vac truck to take returns and suck out mouse hole to 45'. RU cementers, RIH with 2-7/8" tbg, circulate 90 sks class H cement to surface, fill mouse hole with 32 sks cement. RDMO WSU and cementers.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/28/2017 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

Removed standing fluid from inside conductor and mousehole. Filled same with 7 yards of Redi Mix.

INVOICED  
JAN 30 2018

Remarks: ANDALE REDI MIX DENIED TA

Plugged through:

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

SK