

9-17

To: 1 070589
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,285.0000
NE SE NW, SEC. 9, T 20 S, R 16 W/E
3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6412
Operator: Sid Tomlinson
Name & Address: Rt. 4, Box 7695
Twin Falls, Idaho 83301

Lease Name Chlumsky Well # 1
County Pawnee 125.78
Well Total Depth 3870 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 400

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X _____

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 5:15 p.m. Day: 16 Month: 9 Year: 19 88

Plugging proposal received from David Wondra

(company name) Red Tiger Drilling Company (phone) 316-263-1201

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1108-42'
1st plug if 50' into the Arbuckle with 40 sx cement,

2nd plug at 1140' with 50 sx cement, 3rd plug at 420' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:30 a.m. Day: 17 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 3790' with 40 sx cement,

2nd plug at 1140' with 50 sx cement,

3rd plug at 420' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

NOTE: Problem with Dakota but did not flow from surface.

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1988
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 10-4-88

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 22458

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 9-7-88 month day year

API Number 15-145-21,285.0000

OPERATOR: License # 6412 Name Sid Tomlinson Address Rt. 4, Box 7695 City/State/Zip Twin Falls, Idaho 83301 Contact Person Sid Tomlinson Phone (208) 734-9329

NE SE NW Sec. 9 Twp. 20 S, Rg. 16 East 3630 West 2970 Ft. from South Line of Section Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5302 Name Red Tiger Drilling Company City/State Wichita, Kansas

Nearest lease or unit boundary line 330 feet County Pawnee Lease Name Chlumsky Well # 1 Ground surface elevation 2065 feet MSL Domestic well within 530 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water unknown 175 Depth to bottom of usable water 260 345 Surface pipe by Alternate: 1 X 2 Surface pipe planned to be set 365' Conductor pipe required Projected Total Depth 3900 feet Formation Arbuckle

Well Drilled For: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

IF OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 8-26-88 Signature of Operator or Agent Sid Tomlinson Title Owner/Operator

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 365 feet per Alt. 1 X

This Authorization Expires 2-30-89 Approved By AKM 8-30-88

EFFECTIVE DATE: 9-4-88

RECEIVED STATE CORPORATION COMMISSION SEP 22 1988 CONSERVATION DIVISION

Set 365' of 8 5/8 on 9-7-88

NO WW

NE SE NW Sec. 9 Twp. 20 S, Rg. 16 East X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays)

1st plug @ Top Arbuckle feet depth with 40 sxs of cement
2nd plug @ Base Anhydrite feet depth with 50 sxs of cement
3rd plug @ 30' below surf. CSG feet depth with 40 sxs of cement
4th plug @ 0-40 feet depth with 10 sxs of cement
5th plug @ feet depth with sxs of cement
(2) Rathole with 15 sxs (b) Mousehole with 10 sxs

PUSHER David Wardre TD 3870 FORMATION Arbuckle SURFACE PIPE 8 5/8" @ 400 ANHYDRITE 1108' ELEVATION 1142 STARTING TIME & DATE 5:15 PM COMPLETION TIME & DATE 1:30 AM 9-7-88 1st PLUG @ 1140 FT. W/ 50 SX 2nd PLUG @ 420 FT. W/ 40 SX 3rd PLUG @ 40 FT. W/ 10 SX 4th PLUG @ 390 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 MOUSE HOLE CIRCULATED W/ WATER WELL PLUGGED W/ CEMENT COMPANY Halburton TECHNICIAN D.G. 40 SX of 50' in Arb. 60/40 67% Problem w/ Dakota but did not flow from surface