

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

1-22

API NUMBER: 15-159-21,136.0000

SW NW NW, SECTION 27 TOWNSHIP 20 RANGE 7W

OPERATOR LICENSE # 32017 4620 FEET FROM S SECTION LINE
OPERATOR ABC OIL & SALVAGE 4950 FEET FROM E SECTION LINE
NAME & RT. #3, BOX 151
ADDRESS LYONS, KS 67554

LEASE NAME: ENGELLAND #1-A
COUNTY: RICE 111.96
WELL TOTAL DEPTH: 3445'
PIPE: 5 1/2" @ 3445'
SURFACE CASING: 8 5/8" @ 255'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: QUALITY WELL SERVICE
ADDRESS: STERLING, KS LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 10:30 DAY: 22 MONTH: 1 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: RICHARD MCINTYRE
COMPANY NAME: QUALITY WELL SERVICE PHONE: (316) 727-3410
WERE: SAND TO 3300' AND 5 SACKS
35 SACKS AT 1200'
35 SACKS AT 600'
310'-0'

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 3:30 DAY: 22 MONTH: 1 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3300' AND 5 SACKS. SHOT 5 1/2" CASING OFF AT 1637'. PULLED TO 1200', PUMPED 35 SACKS. PULLED TO 600', PUMPED 35 SACKS. PULLED TO 310', CIRCULATED CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL UNITED #3621

I DID OBSERVE THIS PLUGGING.

Jack Luthi
JACK LUTHI

INVOICED
RECEIVED
KANSAS CORPORATION COMMISSION
DATE JAN 29 1997 JAN 29 1997
INV. NO. 47476
1-22
CONSERVATION DIVISION
MAR 27 1997
WICHITA, KS