

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-059-23562-00-00
Spot: SWSWNWSE Sec/Twnshp/Rge: 28-15S-20E
1485 feet from S Section Line, 2475 feet from E Section Line
Lease Name: VERNA DUNN Well #: 1
County: FRANKLIN Total Vertical Depth: 800 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	788		65 SX
SURF	6.25	42		15 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/13/2017 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: REX R. ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: IF CANNOT "BULL HEAD" CMT SQZ DWN THE PROD CSG, WILL RI 1" TBG INSIDE THE PROD CSG TO 730', PMP CMT DWN THRU TBG, CIRC SAME TO SURF, POOH TBG, "TOP OFF" PROD CSG W/ CMT, THEN PRESS UP TO 100 PSI & SWI. WILL RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH" & CLEAN UP LOC.

Plugging Proposal Received By: RYAN DULING Witness Type: NONE
Date/Time Plugging Completed: 11/13/2017 12:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Pumped portland cement down casing, filled up from top to bottom, shut in with valve.

Perfs:

Top	Bot	Thru	Comments
727	733		

RECEIVED
KCC DIST # 3
JAN 31 2018
CHANUTE, KS

RD

Remarks:

Plugged through: CSG

INVOICED
FEB 08 2018

District: 03

Signed

[Signature]
(TECHNICIAN)