

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-059-23236-00-00  
Spot: SENESENE Sec/Twnshp/Rge: 3-16S-20E  
4812 feet from S Section Line, 141 feet from E Section Line  
Lease Name: MCCONNELL Well #: 4  
County: FRANKLIN Total Vertical Depth: 732 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>5150</u>	PROD	2.875	730		103 SX
Op Name: <u>COLT ENERGY INC</u>	SURF	6.25	42		15 SX
Address: <u>PO BOX 388</u> <u>IOLA, KS 66749</u>					

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/13/2017 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL, WELL SERVICES LLC  
Proposal Revd. from: REX R. ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: IF CANNOT "BULL HEAD" CMT SQZ DWN PROD CSG, WILL RI 1" TBG DWN SAME TO 729', THEN PMP CMT DWN TBG AND CIRC SAME TO THE SURF, POOH TBG, "TOP OFF" PROD CSG W/ CMT, PRESS UP TO 100 PSI, AND SWI. WILL RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH" AND CLEAN UP LOC.

Plugging Proposal Received By: RYAN DULING WitnessType: NONE  
Date/Time Plugging Completed: 11/13/2017 12:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Pumped portland cement down casing, filled up from top to bottom. shut in with valve.

Perfs:

Top	Bot	Thru	Comments
664	670		

RECEIVED  
KCC DIST # 3  
JAN 31 2018  
CHANUTE, KS

RD

Remarks:

Plugged through: CSG

INVOICED

FEB 08 2018

District: 03

Signed

[Signature]  
ECCS  
(TECHNICIAN)