

TO: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-101-22294-00-00
 Spot: NESESWSW Sec/Twnshp/Rge: 27-18S-30W
424 feet from S Section Line, 4100 feet from E Section Line
 Lease Name: CONNER Well #: 14-27
 County: LANE Total Vertical Depth: 4620 feet

Operator License No.: 34038
 Op Name: FLATIRONS RESOURCES LLC
 Address: CIRCLEPOINT CORPORATE CNTR II 1
WESTMINSTER, CO 80020

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4220		WITH 2 SX CMT
CIBP		4330		WITH 2 SX CMT
PC	5.5	2150		WITH 330 SX CMT
PROD	5.5	4620	0	WITH 180 SX CMT
SURF	8.625	224		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/10/2018 10:00 AM
 Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.
 Proposal Rcvd. from: BRETT HILDERBRAND Company: FLATIRONS RESOURCES Phone: (785) 871-7311

Proposed Plugging Method: CIBP @ 4330'. CIBP @ 4220'. PUMP 50 SX CMT WITH 100# HULLS. FILL CASING WITH CMT FROM 2100' TO 0'. ATTEMPT TO GET CMT DOWN ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 01/10/2018 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4330' WITH 2 SX CMT. SET CIBP @ 4220' WITH 2 SX CMT. RUN TBG TO 3710' & PUMPED 50 SX CMT & 200# HULLS. PULLED TBG TO 2100' & PUMPED 200 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4545	4554		
4431	4436		
4385	4388		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILFIELD.

Plugged through: TBG

District: 01

Signed Michael Maier
 (TECHNICIAN)

RECEIVED
 JAN 16 2018
 KCC DODGE CITY

INVOICED
 FEB 08 2018