

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-19883-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 15-23S-13E
2425 feet from S Section Line, 4980 feet from E Section Line
Lease Name: SHADEL Well #: 11
County: GREENWOOD Total Vertical Depth: 1763 feet

Operator License No.: 33640
Op Name: HAAS PETROLEUM, LLC
Address: 10551 BARKLEY ST. #307
OVERLAND PARK, KS 66212

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6.625	1730		50 SX
SURF	15.5	16		15 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/10/2018 1:00 PM
Plug Co. License No.: 33557 Plug Co. Name: SKYY DRILLING, LLC
Proposal Rcvd. from: MARK HAAS Company: _____ Phone: (913) 499-8373

Proposed Plugging Method: Pump full of cement from top to bottom

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: PARTIAL
Date/Time Plugging Completed: 01/10/2018 4:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

Ran pipe to 1675', pumped 30 sxs cement, pulled pipe to 800', pumped 20 sxs cement, pulled pipe to 250', pumped 88 sxs cement to surface, casing shot @ 800' & 250', gel spacers between cement plugs.

RECEIVED
KCC DIST # 3
JAN 16 2018
CHANUTE, KS

mtt

INVOICED
FEB 08 2018


Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)



PRESSURE PUMPING LLC
 PO Box 884, Chanute, KS 66720
 620-431-9210 or 800-467-8676

TICKET NUMBER 54895

LOCATION E/Dorado

FOREMAN Brad Butler

FIELD TICKET & TREATMENT REPORT

CEMENT API # 15-073-1983

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
1-10-18	3451	Shadle #11	15	23	13E	Greenwood
CUSTOMER <u>HAAS Petroleum</u>			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS <u>11551 Ash St. Suite 205</u>			<u>760</u>	<u>Chris</u>		
CITY <u>Leawood</u>			<u>713</u>	<u>Jud</u>		
STATE <u>Ks.</u>			<u>692</u>	<u>MARK</u>		
ZIP CODE <u>66211</u>			<u>702</u>	<u>Brad</u>		

JOB TYPE PTA HOLE SIZE _____ HOLE DEPTH Open Hole CASING SIZE & WEIGHT 4 1/2"
 CASING DEPTH 1675' DRILL PIPE _____ TUBING 1" pipe OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Rig up to 1" pipe, Set cement plugs as following along with Gel Spacers

30 SKs @ 1675'
20 SKs @ 800'
88 SKs @ 250' To Surface

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE 0450		PUMP CHARGE	1500.00	1500.00
CE 0002	30	MILEAGE	7.15	214.50
CE 0711	M/C		660.00	660.00
CC 5329	1.38 sacks	60/40 Pozmix cement w/ 4% Gel	16.00	2208.00
CC 5965	400 lbs	Gel & Spacers between Plugs	.30	120.00
WE 0953	7 Hrs	Water Truck	100.00	700.00
				5402.50
			40% discount	-2161.00
			Sub Total	3241.50
			7.5% SALES TAX ESTIMATED	104.76
			TOTAL	3346.26

Ravin 3737

AUTHORIZATION witnessed by Bev Harrell TITLE Rig Pusher DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.