

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-20394-00-00

Spot: SENE

Sec/Twnshp/Rge: 29-29S-17W

1980 feet from N Section Line,

660 feet from E Section Line

Lease Name: FLOSSIE

Well #: 1

County: KIOWA

Total Vertical Depth: 4928 feet

Operator License No.: 3842

Op Name: LARSON ENGINEERING, INC. DBA LAR

Address: 562 W STATE RD 4
OLMITZ, KS 67564

String Size Depth (ft) Pulled (ft) Comments

CIBP 4825 WITH 2 SX CMT

PROD 4.5 4929 2350 WITH 125 SX CMT

SURF 8.625 398 WITH 325 SX CMT

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 01/05/2018 9:30 AM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: DAVID BRADY

Company: QUALITY WELL SERVICE, INC.

Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4825' WITH 2 SX CMT OR 30 SX CMT WITH 100# HULLS. PLUG AT 1080' WITH 10 SX GEL & 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 01/05/2018 12:30 PM

KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

SET CIBP @ 4825' WITH 2 SX CMT. 1ST PLUG AT 1080' WITH 10 SX GEL & 50 SX CMT. COULDN'T PULL PIPE AFTER 1ST PLUG SO CUT BOTTOM 300' OF RECOVERED PIPE. 2ND PLUG AT 420' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Top	Bot	Thru	Comments
4880	4882		
4876	4878		


INVOICED
FEB 08 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed


SA (TECHNICIAN)

RECEIVED
JAN - 9 2018
KCC DODGE CITY